




40	DODGE PLANS SCAN Transmittal	40
 1249640		
Return Ship Address: ID - 75 Springfield IL McGraw-Hill Const Dodge Planroom 1620 S 5th St Springfield, IL, 62703-3171 (217) 528-1444		Information: DR Number: 200900623958 AddendaNumber: ADD03 Version: 7. Title Code: DR Source: ORN: Created By: Tippin, Lois Bid Date: 9/29/2009 SP_Roil_Count: 0 SS_Book_Count: 0 LA_Sheet_Count: 0 SA_Page_Count: 0 Fax_Page_Count: 6
40		40

200900623958
14 9/29

ADDENDUM NO. 3
TO THE PLANS, SPECIFICATIONS AND CONTRACT DOCUMENTS
Entitled

CITY OF DECATUR

M. L. KING WATER MAIN
City Project 03-23, EPA L17-2553

AD3-1 NOTICE

1.01 This Addendum No. 3 dated September 23, 2009 to the plans, specifications and contract documents for the above captioned project, supersedes all contrary and conflicting information in the documents which are hereby supplemented or revised as follows.

AD3-2 WATER MAIN FITTINGS

2.01 Compact fittings meeting the requirements of AWWA C153 Class 350 for 24 inch and smaller, and Class 250 for fittings larger than 24 inch will be allowed as an alternative to the C110 full body fittings, originally specified.

AD3-3 BID SCHEDULE CHANGES

3.01 Under the BID SCHEDULE, page Proposal 3, Item No. 24, change the quantity of "6" gate valve and box" from 14 EA to 15 EA.

3.02 Under the BID SCHEDULE, page Proposal 3, Item No. 25, change the quantity of "hydrant" from 14 EA to 15 EA.

3.03 Under the BID SCHEDULE, page Proposal 5, Item No. 65, change the quantity of "2" HDPE Sch80 or SDC11 conduit directional bored" from 2355 LF to 6000 LF.

3.04 Under the BID SCHEDULE, page Proposal 5, Item No. 67, change the quantity of "fiber optic cable installed in conduit pipe" from "7300 LF" to "7900 LF".

3.05 Under the BID SCHEDULE, page Proposal 6, add Item No. 105 as follows, 1 EA 42" x 42" x 6" tee.

3.06 Remove the original BID SCHEDULE pages Proposal 3 through Proposal 6 and insert the revised BID SCHEDULE REVISED ADDENDUM 3, pages AD-3 Proposal 3 through AD-3 Proposal 6.

AD3-4 ADDENDUM NO. 3

4.01 This Addendum No. 3 consists of Articles AD3-1 through AD3-4.

Bainbridge, Gee, Milanski & Associates, Inc.
Consulting Engineers
1670 S. Taylorville Road

**CITY OF DECATUR
M.L. KING WATER MAIN**

**BID SCHEDULE
REVISED ADDENDUM 3**

Item No.	Quantity	Description	Unit Price	Total Price
1.	1 LS	bond, insurance, mobilization		
2.	1 EA	48" x 30" tee		
3.	1 EA	30" butterfly valve		
4.	1 EA	30" side outlet tee		
5.	2 EA	48" butterfly valve		
6.	3 EA	48" 90° bend		
7.	14 LF	48" pipe with restrained joints		
8.	1 EA	48" x 42" reducer		
9.	1 EA	42" flow meter		
10.	1 EA	42" check valve		
11.	1 LS	42" piping inside concrete vault		
12.	1 LS	concrete flow meter and check valve vault		
13.	7 EA	42" 45° bend		
14.	1 EA	42" x 36" reducer		
15.	1 EA	36" x 36" x 36" tee		
16.	1 EA	36" x 20" reducer		
17.	1 EA	20" tapping sleeve at ML King and Marion		
18.	1 EA	20" gate valve and box with bypass		
19.	1 EA	36" tapping sleeve		
20.	1 EA	36" gate valve and box with bypass		
21.	7 EA	30" gate valve and box with bypass		
22.	1 EA	24" gate valve and box with bypass		
23.	12 EA	16" gate valve and box		
24.	15 EA	6" gate valve and box		
25.	15 EA	hydrant		
26.	725 LF	42" DIP water main with restrained joints		
27.	420 LF	36" DIP water main with restrained joints		

Item No.	Quantity	Description	Unit Price	Total Price
28.	4417 LF	30" DIP water main		
29.	1159 LF	30" DIP water main with restrained joints		
30.	7614 LF	16" DIP water main		
31.	2824 LF	16" DIP water main with restrained joints		
32.	55 LF	12" DIP water main		
33.	140 LF	6" DIP water main with restrained joints		
34.	415 LF	42" casing pipe with 30" DIP water main, restrained joints		
35.	470 LF	26" casing pipe with 16" DIP water main, restrained joints		
36.	28 LF	26" casing open cut with 16" DIP water main, restrained joints		
37.	1 EA	36" x 30" reducer		
38.	1 EA	36" 45° bend		
39.	34 EA	air release valve and vault		
40.	6 EA	30" x 6" x 30" tee		
41.	1 EA	30" x 12" x 30" tee		
42.	12 EA	30" 45° bend		
43.	4 EA	30" 22.5° bend		
44.	1 EA	30" x 16" x 30" tee		
45.	1 EA	30" x 24" x 16" tee		
46.	1 EA	12" x 6" reducer		
47.	1 EA	24" plug		
48.	45 EA	16" 45° bend		
49.	3 EA	16" 90° bend		
50.	9 EA	16" x 6" x 16" tee		
51.	1 LS	connect to existing 16 w/tapping sleeve		
52.	1 LS	connect to 16" on Fairview with tapping sleeve		
53.	1 LS	connect to existing 30" valve at Wabash		
54.	1 LS	connect to existing 6" main on Wabash		
55.	1 LS	connect to existing 30" plug on Grand		
56.	1 LS	connection to pump 5, Incl. 30" pipe		
57.	1 LS	connection to exist 48, remove blind flange		

Item No.	Quantity	Description	Unit Price	Total Price
58.	1 LS	connect to existing 36" main at ML King & Clay		
59.	1 LS	cut, cap and abandon 6" on ML King south of Marlon		
60.	1 LS	cap and abandon existing 6" water main at Wood		
61.	1 LS	fiber optic cable and conduit termination at SWTP		
62.	1 LS	fiber optic cable and conduit termination at Civic Center		
63.	3 EA	Quartzite type pull box		
64.	29 EA	concrete type pull box		
65.	6000 LF	2" HDPE Sch80 or SDR11 conduit directional bored		
66.	11650 LF	2" HDPE Sch80 or SDR11 conduit installed with water main		
67.	7900 LF	fiber optic cable installed in conduit pipe		
68.	1 LS	seedling, fertilizing, mulch		
69.	20 EA	inlet protection		
70.	1 LS	flowable fill at SWTP		
71.	1 LS	remove and replace lighting, flagpoles, etc at SWTP		
72.	3600 SY	remove & replace aggregate base or surface course, Ty A, 8"		
73.	4200 SY	remove & replace PCC pavement, 9"		
74.	10320 SY	remove & replace PCC pavement 11"		
75.	3000 GAL	bituminous material primer		
76.	2380 TON	Hot mix asphalt surface course Mix C, N50		
77.	70 SY	remove & replace PCC Drive, 6"		
78.	2575 SF	remove & replace PCC sidewalk, 4"		
79.	205 SF	remove & replace concrete median surface, 4"		
80.	1645 LF	remove & replace curb & gutter, 6" barrier		
81.	40 LF	remove & replace curb & gutter, 9" barrier		
82.	920 LF	remove & replace curb & gutter, B-6.12		
83.	20 LF	remove & replace curb & gutter, B-6.18		
84.	95 LF	8" DIP sewer w/C-905 DR-18 casing pipe		
85.	22 LF	sanitary sewer replacement, C-900, DR-18, 8"		

Item No.	Quantity	Description	Unit Price	Total Price
86.	22 LF	sanitary sewer replacement, C-900, DR-18, 10"		
87.	44 LF	sanitary sewer replacement, C-900, DR-18, 12"		
88.	40 LF	storm sewer replacement, C-900 DR-18, 4"		
89.	57 LF	storm sewer replacement, C-900 DR-18, 6"		
90.	83 LF	storm sewer replacement, C-900 DR-18, 8"		
91.	220 LF	storm sewer replacement, C-900 DR-18, 10"		
92.	661 LF	storm sewer replacement, C-900 DR-18, 12"		
93.	22 LF	storm sewer replacement, C-905 DR-18, 18"		
94.	1 LS	water main lowering, 6"		
95.	19620 CY	trench backfill		
96.	1 EA	Manhole A-1C, 4' dia		
97.	1 LS	traffic control and protection		
98.	1 LS	erosion control		
99.	1 LS	electrical work at the SWTP, LS		
100.	1 LS	remove and replace traffic signal loops ML King & Wood St		
101.	1 LS	remove and replace traffic signal loops ML King & Prairie St		
102.	1 LS	remove and replace traffic signal loops ML King & Eldorado St		
103.	1 LS	remove and replace traffic signal loops ML King & Grand Ave.		
104.	1 LS	remove and replace traffic signal loops ML King & Garfield Ave.		
105.	1 EA	42"x 42"x 6" tee		
TOTAL ITEMS 1 THROUGH 105				